LEGEND

- EXISTING MAJOR CONTOUR (65)
- EXISTING MINOR CONTOUR
- LIMIT OF GROUND SURVEY
- PROPERTY LINE
- EXISTING CREEK FLOW LINE
- EXISTING GRADE BREAK
- EXISTING STORMDRAIN PIPE (SD)
- EXISTING EDGE OF PAVEMENT/SIDEWALK
- EXISTING BUILDING
- PROPOSED 5'-WIDE GRADED SOIL PATHWAY
- PROPOSED ALUMINUM BRIDGE
- HYDROSEEDED FINISH GRADE

0 120 240
1" = 120'

LAGUNA WETLANDS PRESERVE

LAGUNA PARK

TOMODACHI PARK

CALIFORNIA ROUTE 12

MORRIS STREET

SEBASTOPOL AVENUE

AMERICORPS TRAIL IMPROVEMENTS

SEE SHEET 5

NEW ZIMPHER CREEK BRIDGE SHEET 6

SEE SHEET 4

SEE SHEET 3

8/10 PROPOSED PERGOLA LOCATION (TYP. OF 3)

11/10 RE-GRADE APPROX. 730 LF LENGTH OF EXISTING TRAIL BY EXCAVATING NATIVE GRADE TO 6" AND MIX WITH 3% PORTLAND CEMENT, IMPORT SOIL WITH 3% PORTLAND CEMENT AS NEEDED TO GRADE TRAIL SURFACE TO LEVEL CONDITION, COMPACT TO 98%

(E) FLOATING BRIDGE

9/10 PROPOSED BENCH LOCATION

11/10 RE-GRADE APPROX. 250 LF LENGTH OF EXISTING TRAIL BY EXCAVATING NATIVE GRADE TO 6" AND MIX WITH 6% PORTLAND CEMENT, IMPORT SOIL WITH 6% PORTLAND CEMENT AS NEEDED TO GRADE TRAIL SURFACE TO LEVEL CONDITION, COMPACT TO 98%

9/10 PROPOSED BENCH LOCATION

(E) AMERICORPS TRAIL

PROPOSED STAGING AREA

NEW PUNCHEON CROSSING

9/10 PROPOSED BENCH LOCATION

(E) LAGUNA TRAIL

BACKFILL TRAIL SCOUR HOLES WITH 3/4" DRAIN ROCK - NORTH SEGMENT

11/10 RE-GRADE APPROX. 400 LF LENGTH OF EXISTING TRAIL BY SCARIFYING NATIVE GRADE TO 6" AND RECOMPACTING TO 90%

10/10 RE-GRADE CENTER FIELD TO TRAIL RAMP AND PLACE TIMBER STEPS - NORTH SEGMENT

11/10 RE-GRADE APPROX. 300 LF LENGTH OF EXISTING TRAIL BY SCARIFYING NATIVE GRADE TO 6" AND RECOMPACTING TO 90%

PROPOSED STAGING AREA

TRAIL CONNECTION TO MORRIS STREET

10/10 (13) INDIVIDUAL PINNED TIMBER STEP STEP RUNS SHALL BE 10" MIN. AND SPACED SO THAT THE RISE BETWEEN STEPS IS 6" (DEPENDENT ON RUNNING GRADE)

N

IF BAR DOES NOT MEASURE 1" DRAWING IS NOT TO SCALE - ADJUST ACCORDINGLY

LAST SAVED: 4/29/2021 PLOT DATE: 4/29/2021 PLOT STYLE: ----

P:\2017\1700038_SEBASTOPOL_AMERICORPS_TRAIL\CAD\MODEL\1700038_DESIGN.DWG

AMERICORPS TRAIL IMPROVEMENT PROJECT

CITY OF SEBASTOPOL PLANNING DEPARTMENT
SONOMA COUNTY

QUESTA ENGINEERING CORP.
Civil
Environmental
& Water Resources
(510) 236-6114
FAX (510) 236-2423
questa@questaec.com
P.O. Box 70356 1220 Brickyard Cove Road Point Richmond, CA 94807

95% REGISTERED PROFESSIONAL ENGINEER ANDREW W. MCCONE No. 87049 Exp. 06-30-21 CIVIL STATE OF CALIFORNIA
NOT FOR CONSTRUCTION

Sht:	Rev:	Date:	By:	Description:	App'd:

Design: JP
Drawn: AM
Checked: MH
Appr'd: MH

OVERVIEW & SHEET LAYOUT

SEBASTOPOL
CALIFORNIA

Size D | Project 1700038
Scale: AS NOTED
Date: 06/21/19
SHEET: 2 OF 10